



The Corporation of the Township of Otonabee-South Monaghan  
**Addendum # 1**  
**PW-W-2024-02**

**Resurfacing of Settlers Line and Base Line**

**Date: April 2, 2024**

This is to Acknowledge Receipt of Addendum

Company \_\_\_\_\_

Date Received \_\_\_\_\_

Authorized Signature \_\_\_\_\_

Position \_\_\_\_\_

**This form shall be included in all bid submissions and acknowledged as per Page 9 of the Tender Document**

**The Corporation of the Township of Otonabee-South Monaghan reserves the right to accept or reject all or part of any bid and also reserves the right to accept other than the lowest bid and to cancel this call for bids at any time.**

**This addendum shall form part of the tender document. Please note the following clarifications, and additional item added to this tender.**

#	Question	Response																																																																																																																																												
1	<p>Can the Township please provide a breakdown of how many metres of each size culvert that will be required for items 5.01 and 5.03.</p>	<p>The township <b>may</b> include driveway culverts or culverts determined to be in poor condition. It is the intention of the Township to only replace culverts in poor condition. Bidders shall not assume all culverts will be replaced and the Township reserves the right to increase or decrease these items at any time.</p> <p>As additional information to bidders a list of entrance culverts and centre line culverts has been provided below:</p> <p><b>Base Line – Total Length</b></p> <table border="1" style="width: 100%; border-collapse: collapse; background-color: #e6f2ff;"> <thead> <tr> <th style="text-align: left;">Culvert Type</th> <th>300mm</th> <th>375mm</th> <th>400mm</th> <th>450mm</th> <th>500mm</th> <th>600mm</th> <th>Grand Total</th> </tr> </thead> <tbody> <tr> <td>Entrance Field</td> <td style="text-align: center;">22</td> <td style="text-align: center;">12</td> <td style="text-align: center;">118</td> <td></td> <td></td> <td></td> <td style="text-align: center;">152</td> </tr> <tr> <td>Entrance Road</td> <td style="text-align: center;">15</td> <td></td> <td style="text-align: center;">59</td> <td></td> <td></td> <td></td> <td style="text-align: center;">74</td> </tr> <tr> <td>Crossing</td> <td></td> <td></td> <td style="text-align: center;">86</td> <td style="text-align: center;">38</td> <td style="text-align: center;">17.5</td> <td style="text-align: center;">12</td> <td style="text-align: center;">153.5</td> </tr> <tr style="background-color: #e6f2ff;"> <td><b>Grand Total</b></td> <td style="text-align: center;"><b>37</b></td> <td style="text-align: center;"><b>12</b></td> <td style="text-align: center;"><b>263</b></td> <td style="text-align: center;"><b>38</b></td> <td style="text-align: center;"><b>17.5</b></td> <td style="text-align: center;"><b>12</b></td> <td style="text-align: center;"><b>379.5</b></td> </tr> </tbody> </table> <p><b>Base Line – Count</b></p> <table border="1" style="width: 100%; border-collapse: collapse; background-color: #e6f2ff;"> <thead> <tr> <th style="text-align: left;">Culvert Type</th> <th>300mm</th> <th>375mm</th> <th>400mm</th> <th>450mm</th> <th>500mm</th> <th>600mm</th> <th>Grand Total</th> </tr> </thead> <tbody> <tr> <td>Entrance Field</td> <td style="text-align: center;">3</td> <td style="text-align: center;">1</td> <td style="text-align: center;">14</td> <td></td> <td></td> <td></td> <td style="text-align: center;">18</td> </tr> <tr> <td>Entrance Road</td> <td style="text-align: center;">2</td> <td></td> <td style="text-align: center;">8</td> <td></td> <td></td> <td></td> <td style="text-align: center;">10</td> </tr> <tr> <td>Crossing</td> <td></td> <td></td> <td style="text-align: center;">7</td> <td style="text-align: center;">3</td> <td style="text-align: center;">1</td> <td style="text-align: center;">1</td> <td style="text-align: center;">12</td> </tr> <tr style="background-color: #e6f2ff;"> <td><b>Grand Total</b></td> <td style="text-align: center;"><b>5</b></td> <td style="text-align: center;"><b>1</b></td> <td style="text-align: center;"><b>29</b></td> <td style="text-align: center;"><b>3</b></td> <td style="text-align: center;"><b>1</b></td> <td style="text-align: center;"><b>1</b></td> <td style="text-align: center;"><b>40</b></td> </tr> </tbody> </table> <p>Approximately five (5), road crossings culverts with a diameter of 400mm <b>may</b> require extensions, three (3), road crossing culverts with a diameter of 450mm <b>may</b> require extensions.</p> <p><b>Settlers Line – Total Length</b></p> <table border="1" style="width: 100%; border-collapse: collapse; background-color: #e6f2ff;"> <thead> <tr> <th style="text-align: left;">Culvert Type</th> <th>150mm</th> <th>400mm</th> <th>600mm</th> <th>1500mm</th> <th>Grand Total</th> </tr> </thead> <tbody> <tr> <td>Entrance</td> <td></td> <td style="text-align: center;">71</td> <td></td> <td></td> <td style="text-align: center;">71</td> </tr> <tr> <td>Field Entrance</td> <td style="text-align: center;">8</td> <td style="text-align: center;">16</td> <td></td> <td></td> <td style="text-align: center;">24</td> </tr> <tr> <td>Road Crossing</td> <td></td> <td style="text-align: center;">50.5</td> <td style="text-align: center;">15</td> <td style="text-align: center;">12</td> <td style="text-align: center;">77.5</td> </tr> <tr style="background-color: #e6f2ff;"> <td><b>Grand Total</b></td> <td style="text-align: center;"><b>8</b></td> <td style="text-align: center;"><b>137.5</b></td> <td style="text-align: center;"><b>15</b></td> <td style="text-align: center;"><b>12</b></td> <td style="text-align: center;"><b>172.5</b></td> </tr> </tbody> </table> <p><b>Settlers Line – Count</b></p> <table border="1" style="width: 100%; border-collapse: collapse; background-color: #e6f2ff;"> <thead> <tr> <th style="text-align: left;">Culvert Type</th> <th>150mm</th> <th>400mm</th> <th>600mm</th> <th>1500mm</th> <th>Grand Total</th> </tr> </thead> <tbody> <tr> <td>Entrance</td> <td></td> <td style="text-align: center;">7</td> <td></td> <td></td> <td style="text-align: center;">7</td> </tr> <tr> <td>Field Entrance</td> <td style="text-align: center;">1</td> <td style="text-align: center;">2</td> <td></td> <td></td> <td style="text-align: center;">3</td> </tr> <tr> <td>Road Crossing</td> <td></td> <td style="text-align: center;">4</td> <td style="text-align: center;">1</td> <td style="text-align: center;">1</td> <td style="text-align: center;">6</td> </tr> <tr style="background-color: #e6f2ff;"> <td><b>Grand Total</b></td> <td style="text-align: center;"><b>1</b></td> <td style="text-align: center;"><b>13</b></td> <td style="text-align: center;"><b>1</b></td> <td style="text-align: center;"><b>1</b></td> <td style="text-align: center;"><b>16</b></td> </tr> </tbody> </table>	Culvert Type	300mm	375mm	400mm	450mm	500mm	600mm	Grand Total	Entrance Field	22	12	118				152	Entrance Road	15		59				74	Crossing			86	38	17.5	12	153.5	<b>Grand Total</b>	<b>37</b>	<b>12</b>	<b>263</b>	<b>38</b>	<b>17.5</b>	<b>12</b>	<b>379.5</b>	Culvert Type	300mm	375mm	400mm	450mm	500mm	600mm	Grand Total	Entrance Field	3	1	14				18	Entrance Road	2		8				10	Crossing			7	3	1	1	12	<b>Grand Total</b>	<b>5</b>	<b>1</b>	<b>29</b>	<b>3</b>	<b>1</b>	<b>1</b>	<b>40</b>	Culvert Type	150mm	400mm	600mm	1500mm	Grand Total	Entrance		71			71	Field Entrance	8	16			24	Road Crossing		50.5	15	12	77.5	<b>Grand Total</b>	<b>8</b>	<b>137.5</b>	<b>15</b>	<b>12</b>	<b>172.5</b>	Culvert Type	150mm	400mm	600mm	1500mm	Grand Total	Entrance		7			7	Field Entrance	1	2			3	Road Crossing		4	1	1	6	<b>Grand Total</b>	<b>1</b>	<b>13</b>	<b>1</b>	<b>1</b>	<b>16</b>
Culvert Type	300mm	375mm	400mm	450mm	500mm	600mm	Grand Total																																																																																																																																							
Entrance Field	22	12	118				152																																																																																																																																							
Entrance Road	15		59				74																																																																																																																																							
Crossing			86	38	17.5	12	153.5																																																																																																																																							
<b>Grand Total</b>	<b>37</b>	<b>12</b>	<b>263</b>	<b>38</b>	<b>17.5</b>	<b>12</b>	<b>379.5</b>																																																																																																																																							
Culvert Type	300mm	375mm	400mm	450mm	500mm	600mm	Grand Total																																																																																																																																							
Entrance Field	3	1	14				18																																																																																																																																							
Entrance Road	2		8				10																																																																																																																																							
Crossing			7	3	1	1	12																																																																																																																																							
<b>Grand Total</b>	<b>5</b>	<b>1</b>	<b>29</b>	<b>3</b>	<b>1</b>	<b>1</b>	<b>40</b>																																																																																																																																							
Culvert Type	150mm	400mm	600mm	1500mm	Grand Total																																																																																																																																									
Entrance		71			71																																																																																																																																									
Field Entrance	8	16			24																																																																																																																																									
Road Crossing		50.5	15	12	77.5																																																																																																																																									
<b>Grand Total</b>	<b>8</b>	<b>137.5</b>	<b>15</b>	<b>12</b>	<b>172.5</b>																																																																																																																																									
Culvert Type	150mm	400mm	600mm	1500mm	Grand Total																																																																																																																																									
Entrance		7			7																																																																																																																																									
Field Entrance	1	2			3																																																																																																																																									
Road Crossing		4	1	1	6																																																																																																																																									
<b>Grand Total</b>	<b>1</b>	<b>13</b>	<b>1</b>	<b>1</b>	<b>16</b>																																																																																																																																									

Approximately eight (8), road crossings culverts with a diameter of 400mm may require extensions.

The Township reserves the right to change/modify these items during the award and construction process.

NEW ITEM	Response																									
<p>Upon review under spring conditions the Township has identified Three (3) locations along Base Line that appear to be saturated and will require removal of existing base and sub-base.</p>	<p>Bidders shall note the attached and revised Section No. 5 – Provisional Items, which includes NEW Item No. 5.07 – Road Excavation. Bidders shall remove and replace pages 47 to 49 of the tender document with the attached.</p> <p>The Township reserves the right to change/modify these items during the award and construction process.</p> <p>The approximate location and volume of material to be removed and replaced is captured below:</p> <p><b>Base Line – Road Excavation</b></p> <table border="1" style="width: 100%; border-collapse: collapse; margin: 10px 0;"> <thead> <tr style="background-color: #e1f5fe;"> <th style="text-align: center;">Location</th> <th style="text-align: center;">From</th> <th style="text-align: center;">To</th> <th style="text-align: center;">Unit</th> <th style="text-align: center;">Quantity</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">1</td> <td style="text-align: center;">450m West of Drummond Line</td> <td style="text-align: center;">330m West 65m</td> <td style="text-align: center;">m<sup>3</sup></td> <td style="text-align: center;">1,160</td> </tr> <tr> <td style="text-align: center;">2</td> <td style="text-align: center;">Civic Address #2533 40m West of Civic</td> <td style="text-align: center;">West 100m</td> <td style="text-align: center;">m<sup>3</sup></td> <td style="text-align: center;">250</td> </tr> <tr> <td style="text-align: center;">3</td> <td style="text-align: center;">Address 2215</td> <td style="text-align: center;">East</td> <td style="text-align: center;">m<sup>3</sup></td> <td style="text-align: center;">370</td> </tr> <tr style="background-color: #e1f5fe;"> <td colspan="4" style="text-align: right;"><b>Grand Total</b></td> <td style="text-align: center;"><b>1,780</b></td> </tr> </tbody> </table> <p><b>Special Provision</b></p> <p><b>16. Road Excavation (Base Repairs) - Item 5.07 (PROVISIONAL)</b></p> <p>OPSS MUNI 206 shall apply except as amended below:</p> <p>The unit price bid shall be full compensation for the supply of all equipment, labour and materials necessary for excavating and importing to the limits identified in the above table and as directed by the Contract Administrator.</p> <p>This item shall include excavating and removal of all poor material (assumed 0.450m deep), the importing, grading, and compaction of Granular B Type II (0.450m deep). Granular 'A' will be supplied and paid for under Item 4.02.</p> <p>For bidding purposes, the intention of this item is to determine and complete</p>	Location	From	To	Unit	Quantity	1	450m West of Drummond Line	330m West 65m	m <sup>3</sup>	1,160	2	Civic Address #2533 40m West of Civic	West 100m	m <sup>3</sup>	250	3	Address 2215	East	m <sup>3</sup>	370	<b>Grand Total</b>				<b>1,780</b>
Location	From	To	Unit	Quantity																						
1	450m West of Drummond Line	330m West 65m	m <sup>3</sup>	1,160																						
2	Civic Address #2533 40m West of Civic	West 100m	m <sup>3</sup>	250																						
3	Address 2215	East	m <sup>3</sup>	370																						
<b>Grand Total</b>				<b>1,780</b>																						

the removal of frost susceptible soils, causing frost heaves, and damaged areas due to saturation.